HASSAN DIVISION.

Notification dated 8th June 1933.

Notice is hereby given to the public that the Travellers' Bungalow at Hole-Narsipur will be under special repairs till about the 15th of June 1933. Only one room will be available for occupation to the travellers during the above period.

B. KRISHNA RAO,
Executive Engineer.

— CHITALDRUG SUB-DIVISION.

Notification No. R. 3. P. R. 66—32-33, dated 6th June 1933.

Notice is hereby given that the sealed tenders will be received at the Office of the Assistant Commissioner, Chitaldrug Sub-Division, on any working day up to 3 P.M. on 26th June 1933 for constructing a Village Panchayet Hall at Korlakunte, Challakere Taluk.

An approximate estimate of quantities is given in the following Schedule. The quantities are not guaranteed. The work should be completed by the end of August 1933, showing continuous equal monthly progress.

2. Detailed estimate and plans may be seen at the Sub-Division Office, Chitaldrug on all working days between 11 A.M. and 5 P.M.

3. Every tender must be accompanied by a deposit of Rs. 50 in cash as earnest money and should be superscribed "Tenders for constructing a Village Panchayet Hall at Korlakunte, Challakere Taluk," in default of which, tenders will be rejected.

4. The earnest money of rejected tenders will be returned as early as possible after the tenders are disposed of and in case of accepted tender, it would be held as a part of security.

5. The final acceptance of any tender will rest with the Deputy Commissioner, Chitaldrug District, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

6. The name of the competitor, whose tender has been accepted, will be posted on the Notice Board in the Taluk Office, Chitaldrug Taluk. No enquiries regarding the acceptance or rejection of a tender will be answered.

7. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual agreement, in default of which, his tender will be considered as cancelled.

8. Definite rates against each item of work in the schedule should be noted both in figures and in words.

9. In case, the accepted tenderer quarries stone, earth, Kankar, sand, etc., from Government or Forest land for use on this work, royalty at the rate fixed by the Government will be recovered from his bills.

SCHEDULE.

Name of work	Unit	Total quantity
Earth work excavation for foundation	C.yd.	27
Filling up foundation with rough stone in mud	„	27
Basement by rough stone or split stone in mud	„	14
Superstructure of Burnt Brick in mud	C.ft.	723
Iron girders put up (12" x 6")	No. or C.ft.	2 or 34
Do joists. The distance between joists will be 1 ft. so as to suit pukka terrace.	R.ft.	350
Terrace roofing 9" thick with Burnt Brick in mortar with concreting 3" and plastering over.	S.ft.	4·08
Burnt Brick in mortar parapet with pillers including plastering.	C.ft.	123
Providing teak wood doors panelled with hinges, etc., complete.	S.ft.	40
Providing teak wood windows with battened shutters by 1½" to 1½" ¾ iron bars including iron clamp, etc.	„	48
Mortar plastering the walls both outside and inside ...	„	17·43
White-washing	„	17·43
Providing burnt stone slabs 4" to 6"	„	144
Flooring with Cuddappa slabs 1½" to 2" thick on 3" concrete.	Sqr.	3·58
Mortor pointing the basement	„	1·89
Chacolate painting doors and windows	„	1·42
Cornice work 9" thick all round outside	R.ft.	·86
Stone pillars dressed with carbals, etc.	„	20

Notification No. R. 3. P.R. 66—32-33, dated 6th June 1933.

Notice is hereby given that the sealed tenders will be received at the Office of the Assistant Commissioner, Chitaldrug Sub-Division, on any working day up to 3 P.M. on 26th June 1933 for improving the katte in Belagatta Village in Chitaldrug Taluk. An approximate estimate of quantities is given in the following schedule. The quantities are not guaranteed. The work should be completed by the end of August 1933, showing continuous equal monthly progress.

2. Detailed estimate and plans may be seen at the Sub-Division Office, Chitaldrug on all working days between 11 A.M. and 5 P.M.

3. Every tender must be accompanied by a deposit of Rs. 50 in cash as earnest money and should be superscribed "Tenders for improving the katte at Belagatta Village in Chitaldrug Taluk" in default of which, tenders will be rejected.

4. The earnest money of rejected tenders will be returned as early as possible after the tenders are disposed of and in case of accepted tender, it would be held as a part of security.

5. The final acceptance of any tender will rest with the Deputy Commissioner, Chitaldrug District, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

6. The name of the competitor whose tender has been accepted will be posted on the Notice Board in the Taluk Office, Chitaldrug Taluk. No enquiries regarding the acceptance or rejection of a tender will be answered.

7. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual agreement, in default of which his tender will be considered as cancelled.

8. Definite rates against each item of work in the schedule should be noted both in figures and in words.

9. In case the accepted tenderer quarries stone, earth, kankar, sand, etc., from Government or forest land for use on this work, royalty at the rate fixed by the Government will be recovered from his bills.

Schedule.

No.	Item of work	Unit	Total quantity
1	Bund R L. 59·00 cutting grips to the slopes of Bund to hold new earth.	3 grades	...
2	Earth work to bund including watering and tampering ...	C.yd.	2,090
3	Providing new stone revetment with jelly backing ...	„	152
3 (a)	Resetting old stone revetment with jelly backing ..	„	355
4	Turfing the slopes of bund	S.yd.	1,569
5	Gravel backing behind the revetment	„	210
6	Sundry items fixing grade stones, Index stones, B. M. stones with filling and painting, etc.	Lump sum	
	Waste Weir.		
1	Earth work excavation	C.yd.	27
2	Stone in surki mortar	C.ft.	631
3	Burnt stone slabs, 6" thick roughly dressed and fixed ..	S.ft.	78
4	Surki pointing	Sqr.	4·50
5	Rough stone work	C.yd.	32
6	Providing joggle joints	No.	5
7	Providing the sides with rough stone revetment ..	Lump sum	
8	Draft and approach cleanings	„	...
9	Providing jelly below the apron near the body wall ...	C.yd.	19

H. NARAYANA RAO,
Assistant Commissioner.

MISCELLANEOUS DEPARTMENTS.

THE LIVE STOCK SECTION, DEPARTMENT OF AGRICULTURE.

Notification, dated 7th June 1933.

Notice is hereby given that sealed tenders will be received up to 2 P.M. on Saturday, the 1st July 1933, by the Director of Agriculture, in his office at Seshadri Road, Bangalore, for the supply of all or any of the articles specified in annexure for one year from 1st July 1933